



Air Conditioner Rental - Air Conditioner Installers - Air Conditioner Hire - Heater Hire

FF3 Fan Heater - 3 kw



- 3kW Ductable Fan Heater
- Rugged industrial design
- Stackable, lightweight
- High volume heated air output
- High efficiency incolloy elements for optimum heating and safety
- Running Current 12.5 amps @ 240 volts
- Quiet in operation

Technical Details

Air Flow (m3/hr)	1017 @ 400pa	
Full load current (amp)	12.5 Amps @ 240 volts	
Fuse Rating (amps)	13	
Voltage (ph-volt/Hz)	1-240-50	
Dry Weight (kg)	10	
Dimensions (mm)	Height	360
	Width	300
	Depth	330